

HONG KONG CONSTRUCTION INDUSTRY TRADE TESTING CENTRE 香港建造業工藝測試中心

Mason Intermediate Trade Test Study Material for Written Test

(Version: IMN-SM-EN-01)



Mason Intermediate Trade Test Study Material for Written Test

Version: IMN-SM-EN-01

Disclaimer

No part of this material may be reproduced or transmitted in any form or by any means without the written permission from the Construction Industry Council (CIC). Whilst reasonable efforts have been made to ensure the accuracy of the information contained in this material, the CIC nevertheless would encourage readers to seek appropriate independent advice from their professional advisers where possible and readers should not treat or rely on this material as a substitute for such professional advice for taking any relevant actions. The CIC will not assume any liability in relation to any loss or damage directly or indirectly resulted from unintended or/and unforeseeable use of this document.

This document is provided as reference for test preparation only. Under all circumstances all content in the official test papers, including but not limited to the terms and conditions therein, prevails.

The CIC reserves the right, at its sole and absolute discretion, to change, update or delete the contents in this document at any time without prior notice.

The CIC reserves all rights of final interpretation for any content in this document.

Enquiries

Enquiries on this material may be made to Hong Kong Construction Industry Trade Testing Centre at:

Address: 95 Yue Kwong Road, Aberdeen, Hong Kong

Tel: (852) 2100 9000 Fax: (852) 2100 9090 Email: hkcittc@cic.hk Website: www.cic.hk

Version: IMN-SM-EN-01

Mason Intermediate Trade Test Study Material for Written Test

This study material is a reference for candidate to prepare for attending written test in Intermediate

Trade Test:

- 1. When conducting bedding work, the requirement is that no holes should be found.
- 2. The deviation at the corner should be less than 5mm.
- 3. During stone laying, straight line joint pattern should exist by not exceeding 3 pieces of masonries.
- 4. For a smooth dent surface, it should be no pitted (sand holes) mortar surface.
- 5. Non-compliance to the work requirement is due to lack of understanding to drawings.
- 6. Before works, the necessary preparation work is to allocate required stone materials appropriately in accordance with the drawing.
- 7. If pinholes exist between stones, it may results from inadequate craftsmanship.
- 8. If straight line joint pattern exists by not exceeding 3 pieces of masonries, it indicates that the stone laying work meet the specification.
- 9. If a lot of stones are broken during cutting, it indicates that the stone cutting technique is inadequate.
- 10. Upon completion of stonework, the wall should be smooth.
- 11. The cause of collapsed mortar after mixing is too much water added during mixing.
- 12. Upon completion of work, the stone surface should be clean.
- 13. All cement mortar should be completely used, and no material left.
- 14. Cement mortar should be used up within 1 hour after mixing with water.
- 15. While working at height, in addition to the safety helmet, safety belt and independent lifeline should be properly used.
- 16. Every board or plank forming part of a working platform should be not less than 25mm in thickness.

- 17. To effectively utilize the material, it is expected that all mortar should be completely used, and no excessive material left.
- 18. When working in a group, the right attitude to work with colleagues is to be considerate, work together and develop good relationships.
- 19. In case of foreign object in the eye, clean water should be used to flush the foreign object out of the eye.
- 20. Work under extremely hot and humid environment could easily lead to heat stroke.

Precautions

This document is provided as reference for test preparation only. Under all circumstances all content in the official test papers, including but not limited to the terms and conditions therein, prevails. There are different versions of the test paper, content include but not limited to tools, materials, equipment, drawing, construction details or procedures and different simulated site environments. Candidates should refer to the official test documents during testing.

The CIC reserves the right, at its sole and absolute discretion, to change, update or delete the contents in this document at any time without prior notice.