

Joiner

Intermediate Trade Test

Study Material for Written Test

(Version : IJN-SM-EN-01)



此文件關於細木工中級工藝測試技術知識測試 (筆試) 內容參考資料。
如需索取此文件的中文版本，請致電 2100 9000 與香港建造業工藝測試中心聯絡。

Disclaimer

No part of this material may be reproduced or transmitted in any form or by any means without the written permission from the Construction Industry Council (CIC). Whilst reasonable efforts have been made to ensure the accuracy of the information contained in this material, the CIC nevertheless would encourage readers to seek appropriate independent advice from their professional advisers where possible and readers should not treat or rely on this material as a substitute for such professional advice for taking any relevant actions. The CIC will not assume any liability in relation to any loss or damage directly or indirectly resulted from unintended or/and unforeseeable use of this document.

This document is provided as reference for test preparation only. Under all circumstances all content in the official test papers, including but not limited to the terms and conditions therein, prevails.

The CIC reserves the right, at its sole and absolute discretion, to change, update or delete the contents in this document at any time without prior notice.

The CIC reserves all rights of final interpretation for any content in this document.

Enquiries

Enquiries on this material may be made to Hong Kong Construction Industry Trade Testing Centre at:

Address: 95 Yue Kwong Road, Aberdeen, Hong Kong

Tel: (852) 2100 9000

Fax: (852) 2100 9090

Email: hkcittc@cic.hk

Website: www.cic.hk

Joiner Intermediate Trade Test Study Material for Written Test

This study material is a reference for candidate to prepare for attending written test in Intermediate Trade Test:

1. Skirting board should be securely nailed in order to prevent it loose.
2. When installing lock into the door leaf, the lock should be slightly recessed.
3. During door installation, it is more appropriate to provide a gap around 1.5-2mm between door leaf and door frame.
4. To facilitate the door leaf installation work, it is more convenient to mark job lines with minimal pressure which can be seen by yourself.
5. The swing direction of the door, i.e. door open to the left or right, should follow the plans/drawings or the job lines marked on ground.
6. The edge of the door leaf should be planed slightly slant inward to provide leading edge.
7. To install the door hinge, screws should be tightening screwed and screw head should be level to the surface.
8. Before construction work, it is important to understand the requirements set out in the drawings and plans.
9. Before planing the door leaf and finishing door edge, it is necessary to remove protruding nails and tap nails head under the wood surface with sufficient depth, (i.e. secret nail and concealed nail head), in order to avoid damaging the planing machine or planing tools.
10. To screw fixing a 20mm thick wooden board on a 50mm thick wooden board, the screw should be 50mm long.
11. Before drilling holes on wall, one should check the location of hidden pipes inside the wall.
12. When installing a door frame, the purpose of marking a floor line on the frame is to provide instructions to workers who work for floor finishes.
13. To saw a groove on the flooring, it is more appropriate to use jig saw.

14. To saw timber floor with a required angle, it is more appropriate to use mitre saw with an adjustable angle.
15. According to Factories and Industrial Undertakings Ordinance, every person carrying out construction work should hold valid certificate of Mandatory Basic Safety Training Course for Construction Industry, also known as Green Card.
16. According to Construction Sites (Safety) Regulations, except those specified under regulation, no person under 18 years of age is employed to carry out the construction work.
17. When there is a problem, such as malfunctions, with an electrical tool, worker should stop using it and report to the person in charge/supervisor to arrange repairing.
18. The sawdust and fillings should be clean and put into the rubbish bin after sawing.
19. During at work on construction site, it is inappropriate to consume alcoholic drinks.
20. Securing the chin straps of safety helmet can effectively lower the impact to the head when worker fall from heights.

Precautions

This document is provided as reference for test preparation only. Under all circumstances all content in the official test papers, including but not limited to the terms and conditions therein, prevails. There are different versions of the test paper, content include but not limited to tools, materials, equipment, drawing, construction details or procedures and different simulated site environments. Candidates should refer to the official test documents during testing.

The CIC reserves the right, at its sole and absolute discretion, to change, update or delete the contents in this document at any time without prior notice.