



CiC Life First - Walk the Talk

DfS in Temporary Works

19 March 2025

Hong Kong — Temporary Works forum (HK-TWf)
香港 — 臨時工程論壇



火炭商廈地盤工字鐵斷裂 六旬工人被擊中飛墮4米亡




油塘地盤工
被工字鐵壓中
昏迷





送院搶救無效

- 肇事工字鐵長3.82米、闊0.4米、高0.32米，重886公斤
- 因先拆承托工字鐵的「U Channel」，工字鐵在拆除期間下墜壓斃下方1名工人
- 精進有制定施工方案，但現場沒有木方、鏈式吊索及滑輪；三判依成沒向工人傳遞施工方案

2024.10.31



Permanent Works Design Information



HK  E


THE HONG KONG
INSTITUTION OF ENGINEERS
香港工程師學會



*The Institution
of Structural
Engineers*

ice

- TW Procedures
- BS5975





<http://www.twforum.org.hk>



Temporary Works Forum Hong Kong
Civil Engineering • hong kong



PROPRIETARY FALSEWORK SYSTEMS



Temporary Steel Platforms

A guide to good practice



Publication

Published by HK Temporary Works Forum (HK-TWf)

2018

Proprietary Falsework Systems

A guide to good practice



Reinforcement Cage Design & Construction

A guide to good practice



Publication

Published by Hong Kong Temporary Works Forum (HK-TWf)

Published October 2019

Issue 1



Reference Material





Temporary Works Management Plan

www.cic.hk
www.twforum.org.hk

March 2023


Swiss Cheese Models










DfS on TW: Innovative Engineering - Making it Easier to Build




- DfMA – Reduce risks; Like a factory – repeated operations in a safe & controlled manner
- No welding. No working at height. No working above water
- Saving of hiring pontoons & lifting plants
- Environmental friendly
- Resolved technical issues
- Re-Use of Modular ELS



DfS on TW: Innovative Engineering - Making it Easier to Build






DfS on Temporary Works – MMC, MiMEP & MiC




DfS on Temporary Works – Standardization, Modular ELS



Making it Easier to Build?



We Can Only Systemize if Permanent Works Allow



DfS on Temporary Works



Scaffolders




Steel fixers




Form workers


1. Erect the steel form.
2. Assemble the first 4m high working platform. Tie the working platform to the steel form with lateral stabilizing tube, screw rod and nut at 4m height.




3. Assemble the 4m-8m high working platform.
4. Tie the working platform to the steel form with lateral stabilizing tube, M16 bolt at 8m height.




5. Erect the first 3m aluminium form, tie the working platform passing through the hole on aluminium form with lateral stabilizing tube, strengthening post, screw rod and nut at 2m height of the aluminium form.
6. Release the tie between the working platform and the steel form connected in step 4.



5. Erect the 3m-6.4m aluminium form.
6. Tie the working platform passing through the hole on aluminium form with lateral stabilizing tube, strengthening post, screw rod and nut at 4m height of the aluminium form.





7. After concreting, tie the working platform to the new cast wall with lateral stabilizing tube, wall-tie bracket and anchor bolts.
8. Remove the forms and ties between the forms and the working platform.



RESIDUAL RISK

OVERLAPPING TRADES – AT NO TIME SHALL WALL TIES OR INCLINED PROPS BE REMOVED.


DfS on Temporary Works



Wall Tie Details
at Cladding Stage

Wall Tie Details
for MIC

DfS on Temporary Works – Smart Sites (Technology)




13999 TQF AT PENNY'S BAY (PHASE II)



Precast RC Slab Factory		
Completed	250	100
In Progress	450	700
Not started		
Total		
Steel Frame Factory		
Completed	200	100
In Progress	500	700
Not started		
Total		
MiC Assembly Factory		
Completed	150	50
In Progress	500	700
Not started		
Total		

FABRICATION STATUS

Precast RC Slab Factory		
A1 Rebar and Formwork Completed	100%	100%
A2 Concreting Completed	100%	100%
A3 Dispatched From Concrete Factory to Assembly	100%	100%
Steel Frame Factory		
B1 Steel Material Cut to Size	100%	100%
B2 Welded to Assembly	100%	100%
B3 Delivery from Steel Factory to Assembly	100%	100%
MiC Assembly Factory		
C1 Assembly of Slab and steel Frame Completed	100%	100%
C2 EBM Works completed	100%	100%
C3 External and Internal ABWF Works Completed	100%	100%
C4 Packing Completed and Ready for Delivery	100%	100%



Sensor instrumentation monitoring



Wireless tilting sensor





Temporary Works Control & Management System



Temporary Works Management – A Guide to Good Practice

Reference Material




Temporary Works Management Plan

www.cic.hk
www.twforum.org.hk

March 2023

TW lifecycle



Key personnel

Contractor's
Representative
(CR)

TW Engineering
Manager
(EM)

TW Coordinator
(TWC)

TW Designer
(TWD)

TW Supervisor
(TWS)

Independent
Checking
Engineer (ICE)



Control & Management of Temporary Works

TW Risk Category

Risk Category	TW Complexity	TW Designer	ICE Verification	TW Site Inspection and T4 Sign Off
A	MAJOR / COMPLEX	TWD is normally a reputable and competent engineering design consulting firm or specialist subcontractor	ICE is normally a reputable and competent engineering design consulting firm independent of TWD	TWC (and ICE - required only if specified in the contract)
B	MEDIUM			TWC
C	MINOR / SIMPLE	TWD can be a qualified engineer of appropriate stream of membership of HKIE or equivalent or a competent design engineer with relevant working experience	ICE can be a registered professional engineer (civil, structural or geotechnical as appropriate) with relevant working experience independent of TWD	TWC




TABLE B2 – Risk Category Typical Examples

Typical TW	Examples		
	Risk Category A	Risk Category B	Risk Category C
	MAJOR / COMPLEX	MEDIUM	MINOR / SIMPLE
General	<ul style="list-style-type: none"> Tower crane bases and other support (e.g. wall ties) Propping of existing structures Bridge erection schemes Batching Plant Any works adjacent to operational railways 	<ul style="list-style-type: none"> Warehouses / sheds Temporary site compound facilities Noise enclosures / Temporary roofs 	<ul style="list-style-type: none"> Reinforcement stability checks Minor temporary site compound facilities
Falsework / Formwork	<ul style="list-style-type: none"> Complex falseworks systems or any proprietary falsework system > 20m high Falsework supporting inclined loads Mechanised formwork systems Single sided formwork > 6m high Inclined formwork systems (except minor stairs/cranked beams) Suspended scaffolds / platforms 	<ul style="list-style-type: none"> Any proprietary falsework system 10m-20m high (or >2 storeys) Any proprietary falsework system supporting > 1.4m thick slab Scaffold supporting loading platforms (>5kPa) Working platform (>5kPa) Cantilever scaffold (>0.9m) and 'bridge over' scaffolds > 3m using proprietary system Double sided formwork > 3m high Single sided formwork 3-6m high Column forms > 10m high Complex back-propping systems 	<ul style="list-style-type: none"> Any proprietary falsework system < 10m high (or 2 storeys) Table forms or repetitive formwork systems Scaffold supporting loading platforms (>1.5kPa and < 5kPa) General duty working platform (>1.5kPa and < 5kPa) 'Bridge over' scaffolds using proprietary system < 3m Column forms < 10m high Double sided formwork > 0.4m and < 3m high Single sided formwork > 0.4m and < 3m high Scaffolding access on slopes Weather retaining scaffold structure or subject to high wind loads Simple back-propping systems
Platforms / Ramps / Covers	<ul style="list-style-type: none"> Traffic Decks and vehicle parapets Working platforms for plant / cranes / piling rigs Barging points / Marine loading ramps Steelwork platforms supporting mobile / crawler cranes Temporary steelwork structures over public areas 	<ul style="list-style-type: none"> Earth platforms and ramps (on sloping sites) for construction traffic or crawler crane 	<ul style="list-style-type: none"> Small span platforms with light loading Drilling rig shallow platforms Covers to protect utilities / openings Earth platforms for cranes < 120T
Excavation and Lateral Support	<ul style="list-style-type: none"> Ground support schemes > 4.5m deep Strutted excavations > 4.5m deep Excavations with complex strutting schemes Excavations adjacent to sensitive structures Excavations with strutting imposing high loads on other structures 	<ul style="list-style-type: none"> Ground support schemes 2m – 4.5m deep Strutted excavations 2m – 4.5m deep Open cut excavations > 4.5m deep Major temporary support to utilities suspended over excavations 	<ul style="list-style-type: none"> Ground support schemes < 2m deep Strutted excavations < 2m deep Open cut excavations 1.2m - 4.5m deep (Open cut < 1.2m are exempt unless adjacent to slope or sensitive receivers) Vertical blinding < 3m deep Minor temporary support to utilities suspended over excavations
Geotechnical	<ul style="list-style-type: none"> Deep dewatering and re-charge schemes Loading on existing sea walls Ground improvement schemes Pipe jacking 	<ul style="list-style-type: none"> Pump test design reviews Pile load tests Ground support for mobile crane outriggers 	<ul style="list-style-type: none"> Earth haul roads / platforms < 3m high
Hoardings / Fences / Barriers	<ul style="list-style-type: none"> Catch fans over public areas Catch fans adjacent to operational railways Vehicle parapets 	<ul style="list-style-type: none"> Hoardings / fences > 3m high Catch fans over site area 	<ul style="list-style-type: none"> Hoardings / fences < 3m high Internal hoardings / partitions Non-proprietary edge protection systems / fences / gates
Lifting / Falling Objects	<ul style="list-style-type: none"> Heaving lifting and hoisting schemes > 25T Jacking or underpinning schemes 	<ul style="list-style-type: none"> Temporary lifting and hoisting systems (5-25T) Man cages / general lifting receptacles / cages Hoists Complex lifting frame with complex CoG Complex lifeline systems 	<ul style="list-style-type: none"> Temporary lifting and hoisting systems (<5T) Simple life line systems Scaffolding / tower lifting
Mechanical Works	<ul style="list-style-type: none"> Temporary Ventilation Systems 	<ul style="list-style-type: none"> Support frames for E&M equipment lifts 	<ul style="list-style-type: none"> Temporary drainage systems and diversions Temporary support of miscellaneous temp. E&M equipment (<1T)

Control & Management of Temporary Works

TW Control Document

T1 MASTER SCHEDULE										
Job No.: J584		Project: Contract No. MRE855 Mountain Rail Extension Peak Station and Eastern Approach Tunnels								
T1 Package & No.	TW Package Description	TW Risk Cat	TWD	ICE	TWC / TWCM	TWS	Date Design Reviewed	Related T2	Related T3	Related T4
A1	Contract Wide TW Packages	A	Consultant	ICE 1	Cecilia Singh	Paul Green	-	n/a	-	-
A2	TW Geological Drawings	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
A3	Contract Wide ELS General Notes & Details	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
A4	Instrumentation	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
B	Site Excavation	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
B1	Project Site	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
B2	Hoarding /	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
B3	Project Site	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
B4	Station	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
C	ELS & Silt	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
C1	ELS & Silt	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
C2	ELS & Silt	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
C3	Construction	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
C4	Temporary	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
C5	Settlement	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
C6	Formwork	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
C7	Steel Shutt	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
C8	Formwork	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D	Approach	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D1	Demolition	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D2	Temporary Road Pavement	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D3	D-Wall Gully	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D4	ELS & Silt	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D5	ELS - Shale	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D6	ELS - Box	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D7	Traffic Deck	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D8	Construction	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D9	Formwork	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
D10	Formwork	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
E	Traffic	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
E1	Traffic	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
E2	TTM2 - S	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
E3	TTM2B - S	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
E4	TTM3 - Box	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-
E5	TTM4 - Box	A	Consultant	ICE 1	Cecilia Singh	Adam Ho	-	n/a	T3-0008	-

T2 DESIGN BRIEF									
Job No.: J584		Project: Contract No. MRE855 Mountain Rail Extension Peak Station and Eastern Approach Tunnels							
T1 Ref.No.	D06	Design Package	ELS - Box Culvert Diversion	Design Brief No.	T2-0014				
Brief Description of the Works to be Designed									
Information Attached to Facilitate the Design									
Initiated by TWS									
Temporary Works Risk Category									
Reviewed and Issued by TWC									
Received and acknowledged by TWD									

T3 DESIGN CHANGE									
Job No.: J584		Project: Contract No. MRE855 Mountain Rail Extension Peak Station and Eastern Approach Tunnels							
T1 Ref.No.	D06	Design Package	ELS - Box Culvert Diversion	Change No.	T3-0016				
Location	TTM2 Stage B at Site Area WA6a								
Element of Works	Strut Layer 2 Knee Brace								
Details of Proposed Change	Due to the change in TTM2 Stage A and B, the extent of temporary Box Culvert Diversion completed during Stage A now clashes with the Stage B knee brace. The designer is requested to adjust the knee brace to avoid clash with completed Stage A temp culvert diversion structure								
Design Drawings Affected	Drawing / Sketch No. MRE855/EAT/CON2/TW/3001 Rev C MRE855/EAT/CON2/TW/3004 Rev A								
Initiated by TWS or TWD	Temp Works Supervisor or Designer Rachel Wong Signature Date 11 Sep 2017								
T3 Risk Category	A Obstruction caused by completed temp culvert structure during TTM2 Stage								
Change to be endorsed by	TWD ICE Required design delivery date 18 Sep 2017								
Issued by TWC	Temporary Works Coordinator Tom West Signature Date 13 Sep 2017								
Reviewed / Approved by TWD	Approved Checked and found satisfactory.								
Change Agreed by TWD	Temporary Works Designer James Chan (Consultant 2) Signature Date 18 Sep 2017								
Reviewed / Approved by ICE	Approved The proposed change is found satisfactory. ICE CERTIFIED (ICE Chop)								
Change Certified by ICE	Independent Checking Engineer William Tsang (ICE1) Signature Date 19 Sep 2017								

RELEASED FOR CONSTRUCTION
批准作建造用途
T1 No.: D06 Risk Cat: 風險類別: B
Signature: Tom West Date: 20/9/2017

T3 DESIGN CHANGE									
Job No.: J584		Project: Contract No. MRE855 Mountain Rail Extension Peak Station and Eastern Approach Tunnels							
Diagram showing the proposed permanent diversion of the box culvert and the temporary structure to be removed. It includes labels for 'Stage A As-Built Culvert Structure', '1st STRUT AT WORKING PLATFORM', 'PROPOSED PERMANENT DIVERSION', 'EXISTING CC BOX CULVERT', 'WELDED', 'MARK STRUT', '2 Pairs of 8x6 RIVETERS WITH 5mm T.M. ALL ROUND (TOP)', '254 UC STEEL BRACKET HINGE 6300mm x/4', 'BUTT WELD SPLICING FOR CONTINUOUS WALING', and 'SHEET PILE'. A dimension of 1500 is indicated.									
TYPICAL DETAIL BETWEEN STRUTTING AND SHEET PILE 1/20									

T4 PERMIT TO LOAD / REMOVE									
Job No.: J584		Project: Contract No. MRE855 Mountain Rail Extension Peak Station and Eastern Approach Tunnels							
T1 Ref.No.	C03	Design Package	Construction Decking - Station	Permit No.	T4-0020				
Location	Construction Decking - Station								
Element of Works	Construction Deck B at Eastern Portion of WA6a								
Extent of Operation and Construction Activity	Partially completed construction deck B as demarcated in the attached markup plan.								
Constructed in accordance with documents	Drawing / Sketch No. MRE855/EAT/CON1/TW/6101 Rev C MRE855/EAT/CON1/TW/6111 B MRE855/EAT/CON1/TW/6112 C MRE855/EAT/CON1/TW/6121 A MRE855/EAT/CON1/TW/6122 A T3 Design Changes T3-0014 T3-0019 Other Reference Documents Construction Method Statement for Construction Decking (Station)								
Permit to Load Initiated by TWS	The above temporary works have been checked by me and as far as I can ascertain they are in accordance with the documents listed above. Temp Works Supervisor James Steel Signature Date 28 Sep 2017								
Permit to Remove Initiated by TWS (if required)	NOTE: Required only if the Temporary Works are still loaded during removal. The above temporary works have been checked by me and may be safely removed. Temp Works Supervisor Signature Date								
Permit to Load endorsed by TWC / TWCM	TWC remarks (if any) Checked and found satisfactory The above temporary works have been checked by me and as far as I can ascertain they are in accordance with the documents listed above. Temporary Works Coordinator Adam Ho Signature Date 2 Oct 2017								
Permit to Remove endorsed by TWC / TWCM (if required)	The above temporary works have been checked by me and may be safely removed. Temporary Works Coordinator Signature Date								
Permit to Load Certified by ICE (Risk Cat A only)	ICE remarks (if any) Checked and found satisfactory The above temporary works have been checked by me and as far as I can ascertain they are in accordance with the documents listed above. Independent Checking Engineer William Tsang (ICE1) Signature Date 2 Oct 2017								



Temporary Works e-Training

Temporary Works Overview

Level 1

Temporary Works e-Training – Level 1 – TW Overview

Click to gain a high level understanding of each of the key roles defined in the TWMP procedure

If you are appointed into any of these roles you should read and understand the TWMP procedure to have more detailed understanding of your responsibilities and the responsibilities of others under the procedure

Contractor's Representative (CR)

Temporary Works Supervisor (TWS)

Temporary Works Co-ordinator (TWC)

Independent Checking Engineer (ICE)

Temporary Works Designer (TWD)

Engineering Manager (EM)

Temporary Works e-Training – Level 2A – People + Responsibilities

The lifecycle duration for some types of TW may only span several weeks

TW Lifecycle Planning & Design

... whilst other types of TW can span months or even years

Common problems:

- TWMP procedure actions not taken at the right timing expected under the TWMP procedure
- Individuals focus on short term day to day goals losing sight of the long term TW objectives
- Insufficient time increases the likelihood of mistakes and shortcuts in TW decision making

Temporary Works e-Training – Level 2B – TW Lifecycle Planning & Design

Proper discharge of the duties of a TWS or TWC under the TWMP Procedure is challenging.

All TWSs & TWCs require adequate recognition, training and support to properly carry out their duties.

If you are a CR or EM, are you actively supporting your TWSs and TWCs to do the right thing in accordance with the TWMP Procedure?

TWSs and TWCs are subjected to pressure to:



- turn a blind eye
- back down from doing what is right
- avoid pointing out potential risks

TWSs and TWCs cannot be expected to stand up to these pressures on their own. They need the technical & authoritative support of their senior management, especially the CR and EMs.

To illustrate the types of pressures TWSs & TWCs are subjected to, please read and see what actions you would take in the following case study.

Temporary Works e-Training – Level 2C – TW Construction and Change

Industry Sharing





**Temporary Works
outcomes are
within our control**



<http://www.twforum.org.hk>



Temporary Works Forum Hong Kong
Civil Engineering • hong kong