



HK CIC

DfMA & MiC from Prototype Demonstrations to Delivery at Scale

Aurélie CLERAUX – Head of Modular Construction,
Innovation and Digital Transformation

**BOUYGUES
BATIMENT**

INTERNATIONAL

Shared innovation

Bouygues Organisation



A member of Bouygues Construction

More than 15 subsidiaries including



And many more: AWE, BYTHAI, Americaribe...

World context



- Increase of world population: need to deliver housing quickly
- Lack of Productivity in the construction industry
- Lack of skilled labour
- New market players in the modular construction sector

MODULAR CONSTRUCTION is THE solution

TO BUILD QUICKER, BETTER, CHEAPER, SAFER, GREENER

A MAJOR INNOVATION EXPLAINED IN 5 POINTS



— FASTER

By industrialising and building offsite around 50% of a project, it removes any loss of time on site due to poor environmental or weather conditions.

— BETTER

Each module is manufactured under strict quality control and checks. Each unit is entirely pre finished with fit-out and façade treatment. All defects are managed prior to handover to site which ensures lower maintenance cost during the lifecycle of the building.

— COST EFFECTIVE

Increased productivity and design optimisation from the start significantly reduces the need for large teams on site. A shorter construction programme means a quicker handover, leading to earlier revenues and reduced financial costs.


— SAFER

Health and Safety is our number one priority and Modular Solutions provides a more protected working environment for our teams, reducing occupational health risks and risks from working at height.


— GREENER

Waste is reduced on site by 70%. Traffic and disruption to local residents is also reduced with less deliveries, less noise and dust.

Panelised to volumetric



Frame Systems



Panel Systems



Pods



Volumetric





FEASIBILITY

Working closely with our clients, we explore the true possibilities of the project. We analyse the affordability, programme, finance viability as well as the transportation and logistics and advise on the best layout and modules structure.



DESIGN & PRE-CONSTRUCTION

The design process is developed with our in-house engineering team and the architect, to optimise the modular design and coordination of trades.



MANUFACTURING

Each unit is manufactured in a quality controlled factory environment. Once completed, the module is transported for the installation of internal and external finishes.



INSTALLATION

It is then ready to be assembled to the site, where it is stacked as per the sequencing programme and to form its structure.

— FEASIBILITY

- Working closely with our clients, we explore the true possibilities of the project.
- We analyse the affordability, programme, finance viability as well as the transportation and logistics and advise on the best layout and modules structure.



FEASIBILITY AND DESIGN

Depending on site location, project type, site constraints, and transportation limitations, we provide a bespoke service of in-house technical & patented solutions.



STEEL



HYBRID




CONCRETE

DESIGN AND PRE CONSTRUCTION

- The design process is developed with our in-house engineering team and the architect, to optimise the modular design and coordination of trades.



— EXAMPLE OF
MODULARISATION



— MANU- FACTURING

- Each unit is manufactured in a quality controlled factory environment.
- Once completed, the module is transported for the installation of internal and external finishes.






**MANUFACTURING
IN OUR
DEDICATED YARD**

— INSTALLATION



- It is then ready to be assembled to the site, where it is stacked as per the sequencing programme and to form its structure.






**INSTALLATION AND
TRANSPORTATION
FROM 2.5M WIDE...**

UP TO 4.5M WIDE!




HUB ATLANTIC



MOROCCO

HUB PACIFIC



MALAYSIA
SINGAPORE

COUNTRY SPECIFIC



CARIBBEAN

CARIBBEAN



**A PRODUCT
APPROACH
WITH TURNKEY
SOLUTIONS**

50+ BOUYGUES REFERENCES

— HOTELS

Citizen M Shoreditch — London, 2016
Hotel Crowne Plaza — Singapore, 2016

— RESIDENTIAL

Clement Canopy — Singapore, 2018
Woodleigh Lane – Singapore, 2021
Serangoon Avenue 1 – Singapore, 2021
Peruma – Singapore, 2021

— STUDENT HOUSING

Canterbury Riverside – UK, 2021
Victoire Daubie — La Verrière, 2016
Crous — Reims, 2016
Crous — Arras, 2015
Oniris — Nantes, 2015
Heinlex – Saint-Nazaire, 2015
Djinn – Le Bourget du Lac, 2014

— MILITARY HOUSING

Catalpa — 30+ projects in France, 2016/2018

— EDUCATION

Collège – Clisson
Lycée Du Sud Loire – Clisson
Campus Valrose – Nice
National Skills Academy For Construction – London
BCA Academy – Singapore, 2021

— ADMINISTRATION

Base Logistique – Saint-Priest
Maison Des Associations (bât A) – Saint-Nazaire

— HEALTHCARE

Nursing Home – Singapore, 2017

— OFFICES

Zac De La Fontaine (Ilot HI) – Orléans

— PRISON

Prison D’orbe – Genève

— SOCIAL HOUSING

Alexandra House YMCA Croydon – London, 2012



288 modules

CROWNE PLAZA EXTENSION A FIVE STAR HOTEL / Singapore

- 243 hotel rooms
- 288 modules
- 10 storey hotel next to Changi Airport
- Gross Floor Area: 10,000 m²
- 17 month programme
- Module type: steel
- Completed in July 2016

276 modules

WOODLAND CRESCENT Nursing home/ Singapore

- 243 beds
- 276 modules
- 2 storeys podium built in-situ
- Gross Floor Area: 9,000 m²
- 15 month programme
- Module type: hybrid steel / concrete
- Completed in 2017
- Weight of one module: between 10 and 15 tons



CLEMENT CANOPY SINGAPORE

Located close to Singapore city centre, Clement Canopy is an iconic project for the city.

- 505 luxury residential apartments
- 1,899 modules
- 40 storey tower
- Gross Floor Area: 46,000 m²
- 36 month programme
- Module type: concrete
- Topping out in April 2018
- To be completed in April 2019



46,000 m²



BLOCK 2
17-48

17-11-49

get bore



834 apartments

WOODLEIGH LANE RESIDENCES Singapore

- 834 apartments
- 2,514 modules
- 7 x 14 – 15 storey blocks
- Gross Floor Area: 58,641 m²
- 33 month programme
- Module type: concrete
- To be completed in October 2020



613 apartments

SERANGOON North Avenue 1 Singapore

- 613 apartments
- 2,012 modules
- 5 x 15 storey blocks
- Gross Floor Area: 47,270 m²
- 30 month programme
- Module type: concrete
- To be completed in July 2020



356 apartments

— PERUMAL Singapore

- 356 apartments
- 842 modules
- 24 storey blocks
- Gross Floor Area: 16,161 m²
- 30 month programme
- Module type: concrete
- To be completed in June 2020

BCA ACADEMY PHASE 2 INTENSIFICATION WORKS SINGAPORE

Institutional Development

- 7 storey Zero Energy Building (ZEB) constructed with Mass Engineering Timber (MET) system
- 16 storey Super Low Energy Building (SLEB) constructed with Advanced Precast System (APCS), Prefabricated Prefinished Volumetric Construction (PPVC) system, and Passive Displacement Ventilation (PDV) system
- Gross Floor Area: 21,800m²
- Fast track 18 months construction programme
- Module type: concrete – 156 modules
- To be completed in June 2021



Innovative Building

CANTERBURY — UNITED KINGDOM

- Student accommodation
- 491 bedrooms
- 430 modules
- Gross Floor Area: 11,897 m²
- Start of modules manufacturing 01/04/2020
- To be completed in September 2021

11,897 m²





R&D and INNOVATION

For MODULAR
CONSTRUCTION

Many challenges to tackle

Technical development

- Structure
- Fire
- Acoustic
- Thermal performance
- Carbon
- Air tightness

Digital Thread for Design for Manufacturing & Assembling... and Disassembling

- Automatic, Generative design
- Full coordination with BIM 3D, 4D and 5D
- Automatic procurement, BOM
- Methods of assembly

Smart Factory, 4.0

- LEAN Manufacturing
- Logistics & materials tracking
- QA, QC, Safety, Activity monitoring

**R&D
INNOVATION
DIGITALISATION**



Challenge 1

Technical Developments



Develop solutions without existing regulations for offsite construction





Shared **innovation**

Technical developments

Example: Modular in the UK



Mock up studio




Technical developments

Robustness and disproportionnate collapse

Compliance with local Standards:

- Structure
- Fire
- Acoustic
- Thermal
- Carbon

Robustness check





Technical developments



Compliance with local Standards:


- Structure
- Fire
- Acoustic
- Thermal
- Carbon




Technical developments



Standard partition



Modular partition



Compliance with local Standards:

- Structure
- Fire
- Acoustic
- Thermal
- Carbon


Technical developments



Compliance with local Standards:

- Structure
- Fire
- Acoustic
- Thermal
- Carbon

 **PPVC**
- 12%




*Comparison TRADI/PPVC
Tradi made of concrete VS hybrid PPVC*

Technical developments



Compliance with local Standards:

- Structure
- Fire
- Acoustic
- Thermal
- Carbon



1,2 tCO₂e

LCA done for a project based in Manchester

Technical developments



Compliance with local Standards:

- Structure
- Fire
- Acoustic
- Thermal
- Carbon

The Assurance Scheme comprises:

- Assessment and accreditation against best practice by Lloyd's Register EMEA.
- A 60 year durability assessment by BLP Insurance.
- A web based database comprising properties constructed under the BOPAS scheme with details of construction.

Accreditation undergoing:

- BOPAS



Technical developments



- Need for collaborative research works between government, universities, private companies (consultants, GC, architects)
- Let's NOT stop at R&D but let's make this become real through new regulations and guidelines, adapted to modular construction and offsite construction

Challenge 2

DfMA + D


Design for Manufacturing and Assembling and
Disassembling



Shared **innovation**

Today in BIM


**Design Teamwork
3 Disciplines to
develop PPVC
collaboratively**




MECHANICAL SERVICES



ARCHITECTURAL FINISHES



STRUCTURAL MODEL



COMBINED MODEL



Tomorrow: Library of components




Challenge 3

Smart Factory




Shared **innovation**

REAL TIME MONITORING OF PRODUCTION



PER TASK, PER MODULE
START / STOP BUTTON



CENTRAL MONITORING PLATFORM

— QUESTIONS ?

AURÉLIE CLERAUX

- HEAD OF MODULAR CONSTRUCTION
- CHIEF INNOVATION and DIGITAL OFFICER

a.cleraux@bouygues-construction.com

